

TOWN OF ANDOVER


Department of Public Works
 5 Campanelli Drive
 Andover, MA 01810
 (978) 623-8700
www.andoverma.gov

UPDATED: October 13, 2022

Town of Andover DPW- 2022 Paving Projects

This list will be updated with more streets periodically as the paving season progresses.


Street Name	From Street	To Street	Length (FT)	Width (FT)	Treatment
LOWELL STREET	BEACON STREET	KIRKLAND DRIVE			M/O
CHANDLER ROAD	I-495 OVERPASS	GREENWOOD ROAD			M/O
GREENWOOD ROAD	NORTH STREET	CHANDLER ROAD			M/O
NORTH STREET	CHANDLER ROAD	JOSEPH STREET			M/O
NOEL ROAD	BEACON STREET	DEAD END			M/O
COLONIAL DRIVE	MAIN ST	PRIVATE	290	32	Reclaim
COLONIAL DRIVE	PRIVATE	PRIVATE	264	32	Reclaim
COLONIAL DRIVE	PRIVATE	PATRIOT DR	699	32	Reclaim
COLONIAL DRIVE	PATRIOT DR	CUL DE SAC	1027	32	Reclaim
DASCOMB ROAD	STEEPLE CT	OSGOOD ST	261	30	M/O
DASCOMB ROAD	OSGOOD ST	CARRIAGE HILL RD	707	30	Reclaim
DASCOMB ROAD	CARRIAGE HILL RD	PARTRIDGE HILL RD	317	30	Reclaim



TOWN OF ANDOVER

Department of Public Works
 5 Campanelli Drive
 Andover, MA 01810
 (978) 623-8700
www.andoverma.gov


Street Name	From Street	To Street	Length (FT)	Width (FT)	Treatment
DASCOMB ROAD	PARTRIDGE HILL RD	SURREY LN	251	30	Reclaim
GARDNER AVENUE	HIDDEN RD	MAIN ST	603	19	Reclaim
GREENWOOD ROAD	HIGH PLAIN RD	CANDLEWOOD DR	870	30	M/O
GREENWOOD ROAD	CANDLEWOOD DR	COTTONWOOD CIR	1395	30	M/O
GREENWOOD ROAD	COTTONWOOD CIR	TIFANNY LN	891	30	M/O
GREENWOOD ROAD	TIFANNY LN	LOWELL ST	1249	30	M/O
HAMPTON LANE	RUTGERS RD	CUL DE SAC	712	24	M/O
HIDDEN ROAD	MAIN ST	FORBES LN	965	24	Reclaim
HIDDEN ROAD	FORBES LN	HIDDEN WAY	387	24	Reclaim
HIDDEN ROAD	HIDDEN WAY	GARDNER AVE	520	24	Reclaim
HIDDEN ROAD	GARDNER AVE	LANTERN LN	273	24	Reclaim
HIDDEN ROAD	LANTERN LN	SUNSET ROCK RD	763	24	Reclaim
HIDDEN ROAD	SUNSET ROCK RD	PIKE SCHOOL RD	1013	24	Reclaim
HIDDEN ROAD	PIKE SCHOOL RD	MAIN ST	841	24	Reclaim
LINDA ROAD	MAIN ST	NANCY CIR	1033	27	Reclaim
LINDA ROAD	NANCY CIR	ROCKY HILL RD	584	27	Reclaim



TOWN OF ANDOVER

Department of Public Works
 5 Campanelli Drive
 Andover, MA 01810
 (978) 623-8700
www.andoverma.gov

Street Name	From Street	To Street	Length (FT)	Width (FT)	Treatment
NANCY CIRCLE	LINDA RD	CUL DE SAC	755	26	Reclaim
PATRIOT DRIVE	COLONIAL DR	CUL DE SAC	923	26	Reclaim
RED GATE DRIVE	TEWKSBURY ST	CUL DE SAC	488	27	Reclaim
RINDGE ROAD	RUTGERS RD	CUL DE SAC	618	28	M/O
ROCKY HILL ROAD	LINDA RD	DEAD END	1140	23	Reclaim
RUTGERS ROAD	HAGGETTS POND RD	RUTGERS RD-02	821	35	M/O
RUTGERS ROAD	RUTGERS RD-01	RINDGE RD	1317	35	M/O
RUTGERS ROAD	RINDGE RD	HAMPTON LN	362	35	M/O
RUTGERS ROAD	HAMPTON LN	SHEFFIELD CIR	1070	35	M/O
RUTGERS ROAD	SHEFFIELD CIR	LOWELL ST	668	35	M/O
SHEFFIELD CIR	RUTGERS RD	CUL DE SAC	515	25	M/O
STEEPLE CT	DASCOMB RD	CUL DE SAC	595	26	M/O



TOWN OF ANDOVER

Department of Public Works

5 Campanelli Drive

Andover, MA 01810

(978) 623-8700

www.andoverma.gov

Treatment:

Reclaim - Reclamation Explanation

Catch basins, manholes, and gate boxes (the small 5" diameter metal covers you see in the road) are dug up and lowered to a depth of 12" below the surface. We then grind up and re-level the existing roadway and base soils under the roadway to depth of 8"-12". Catch basins, manholes, and gate boxes are then adjusted to be flush with the new roadway. Then we pave 2" of new base (binder) course asphalt and 1.5" of new top (finish) course asphalt over the new roadway base.

Reclamation Steps

- A. Reclaim to 8-12" depth
- B. HMA 4" thick
- C. Castings Removed & Reset
- D. Water Boxes Removed & Reset

M/O - Mill & Overlay Explanation

We grind away and reuse or recycle 2" of the existing roadway. Catch basins, manholes, and gate boxes (the small 5" diameter metal covers you see in the road) are then adjusted to be flush with the new roadway. Then we pave 2" inches of new asphalt over the existing roadway.

Mill & Overlay Steps

- A. Cold Mill to 2.0" depth
- B. HMA avg. 2" thick
- C. Castings Adjusted for overlay
- D. Water Boxes Adjusted for overlay

Overlay 1.5" Explanation

Catch basins, manholes, and gate boxes (the small 5" diameter metal covers you see in the road) are adjusted to be flush with the new roadway. Then we pave 1.5" inches of new asphalt over the existing roadway.

Overlay 1.5" Steps

- A. Castings Adjusted for overlay
- B. Water Boxes Adjusted for overlay
- C. HMA avg. 1.5" thick